

## GRID CONTROL RECTIFIER TUBE

## Xenon Gas Filling



BOTTOM VIEW



Maximum Rated Anode Current		
D-c. Meter Value-Continuous	6.4	amps
D-c. Meter Value-Overload less than 3 sec.	12.8	amps
Averaging Time	6	secs
Oscillograph Peak-Continuously recurring	77	amps
Peak Forward Voltage (Max. Instantaneous)	1000	volts
Peak Inverse Voltage (Max. Instantaneous)	1250	volts
Max. Commutation Factor (V/usec x A/usec)	130	
Tille se end		
Filament	2.5	volts
Voltage Current		amps
Heating Time (minimum)		secs
Hearing Time (minimum)		5003
Average Arc Drop		
Average Tube	11	volts
Highest Tube	15	volts
Anode Starting Voltage @ +3V d-c grid voltage		
Average Tube		volts
Highest Tube		volts
Max. Anode Reverse Current	100	uamps
Grid Characteristics		
Critical Grid Voltage @ 1000 p.f.v.	-2.0 to -15	volts
Critical Grid Current	Less than 20	uamps
Grid-Anode Capacitance	approx. 5	
Grid-Filament Capacitance	approx. 21	uuf
Maximum Negative Grid Voltage	100	volts
Deionization Time	Less than 1000	usecs
Max. Peak A-c Fault Current	Dead man 1000	45000
(Max. duration O.1 sec.)	770	amps
Ambient Temperature Limits	-55° to +75°	
Overall Dimensions	2-3/16" x 9-1/4"	max,
Weight	8	025.
Connections		
Filament and Grid	Lug type	a base
r mannent and or a	• .	

The filament must be lit before drawing d-c. load current

The anode is designed to operate at red heat when under full load. All of the above values are for returns to the filament transformer center tap. Filament pin #2 should be negative with respect to pin #3 during the anode conduction period.

C1-5 cap (0.56" dia.) with ceramic insulator.

The Engineering Manual contains additional information which should be considered in the circuit design.

ELECTRONS, INCORPORATED 127 Sussex Avenue Newark 3, New Jersey